

भारत सेवा संस्थान

पत्रांक 281 / बी0एस0एस0 / 2023-24

दिनांक 04-07-2023

निविदा सं० 01 / 2023

चन्द्रभानु गुप्त नवचेतना केन्द्र भवन, 10-अशोक मार्ग, लखनऊ में तीन नये टॉयलेट का निर्माण कार्य कराये जाने हेतु मोहरबंद निविदाएं दिनांक 20.07.2023 अपराह्न 02:00 बजे तक आमंत्रित की जाती है।

सभी इच्छुक ठेकेदार अपनी निविदा के साथ कार्य अनुभव, फर्म का रजिस्ट्रेशन, जी0एस0टी0 रजिस्ट्रेशन, आधार कार्ड, पैन कार्ड की सत्यापित प्रति लगाते हुए रु० 20000 /- (रुपया बीस हजार मात्र) की (Earnest Money) धरोहर राशि, बैंक ड्राफ्ट/बैंकर चेक जो "भारत सेवा संस्थान" के नाम से लखनऊ में देय हो, जमा करेंगे। प्राप्त निविदाएं दिनांक 20.07.2023 को सायंकाल 03:00 बजे भारत सेवा संस्थान, 2-राणा प्रताप मार्ग, मोतीमहल, लखनऊ में बोर्ड के समक्ष खोली जायेंगी, जिसमें निविदाकर्ता/फर्म के प्रतिनिधि अपनी उपस्थिति सुनिश्चित करेंगे।

महामंत्री

भारत सेवा संस्थान

2-राणा प्रताप मार्ग

मोतीमहल, लखनऊ-226001

NAVCHATNA KENDRA 10 ASHOK MARG, LUCKNOW , (U.P.)

S.NO	ITEMS	NO	LENGTH	WIDTH	HEIGHT	QUANTITY	UNIT
1	Earth work excavation of soil for foundation of boundary wall all material,labour,t&p etc complete						
	long wall	2	4.03	0.75	0.75	4.53	CUM
	short wall	2	1.31	0.75	0.75	1.47	CUM
				TOTAL		6.68	CUM
2	P.C.C.1:5:10 cement coarse sand &40mm stone ballast for base foundation wall&pillar with all material,labour ,t&p etc complete						
	long wall	2	4.03	0.75	0.15	0.91	CUM
	short wall	2	1.31	0.75	0.15	0.29	CUM
				TOTAL		0.27	CUM
3	M-150 brick work 1:6 cement coarse sand mortar in foundation with all material,labour ,t&p etc complete						
	long wall	2	3.97	0.69	0.15	0.82	cum
	short wall	2	1.37	0.69	0.15	0.28	cum
	long wall	2	3.86	0.58	0.15	0.67	cum
	short wall	2	1.48	0.58	0.15	0.26	cum
	long wall	2	3.74	0.46	0.15	0.52	cum
	short wall	2	1.6	0.46	0.15	0.22	cum
	long wall	2	3.63	0.35	0.15	0.38	cum
	short wall	2	1.71	0.35	0.15	0.18	cum
	long wall	2	3.51	0.23	0.45	0.73	cum
	short wall	2	1.83	0.23	0.45	0.38	cum
	step	1	1	0.6	0.15	0.09	cum
	step	1	1	0.3	0.15	0.05	cum
				total		4.57	cum
4	R.C.C 1:1.5:3 cement ,coarse sand &20mm stone grit mortar in plinth band excluding centering & shuttering with all material,labour ,t&p etc complete						
	long wall	2	3.51	0.23	0.15	0.24	cum
	short wall	2	1.83	0.23	0.15	0.13	cum
				total		0.37	cum
5	M-150 brick work 1:3 cement coarse sand mortar in superstructure with all material,labour ,t&p etc complete						
	pillar	2	0.23	0.23	2.74	0.29	cum
	pillar	2	0.23	0.23	2.65	0.28	cum
	long wall	1	3.05	0.12	2.74	1.00	cum
	long wall	1	3.05	0.12	2.65	0.97	cum
	short wall	2	1.83	0.12	2.74	1.20	cum
	parapher above g.c sheet	1	3.51	0.23	0.23	0.19	cum
	parapher above g.c sheet	2	2.06	0.23	0.23	0.22	cum
				total		4.15	cum
	ded door	1	0.75	0.12	2.1	0.19	cum

NAVCHATNA KENDRA 10 ASHOK MARG, LUCKNOW , (U.P.)

	venti	1	0.6	0.12	0.45	0.01	cum
					total ded	0.22	cum
					net total	3.93	cum
6	R.C.C 1:1.5:3 cement ,coarse sand & 20mm stone grit mortar in lintel band door, ventilator excluding centering & shuttering with all material,labour ,t&p etc complete						
	door lintel	1	1.21	0.23	0.15	0.04	cum
	venti. Lintel	1	1.06	0.23	0.15	0.04	cum
	sun shade of door	1	1.2	0.45	0.08	0.01	cum
	sun shade of ventilator	1	1.06	0.45	0.08	0.04	cum
					total	0.16	cum
7	Tor steel for r.c.c. work						
	0.37+0.16=0.53	0.53	1.00%	7850		52.01	kg
8	Cutting bending ,binding & placing at site of reinforcement						
					same as item no 7	52.01	kg
9	Centering & shuttering of r.c.c. work for door lintel	1	1.21	0.12		0.15	sqm
		2	1.21	0.15		0.36	sqm
		1	1.21	0.45		0.54	sqm
		2	0.45	0.08		0.07	sqm
	venti lintel	1	1.06	0.12		0.13	sqm
		2	1.06	0.15		0.32	sqm
		1	1.06	0.45		0.48	sqm
		2	0.45	0.08		0.07	sqm
					total	2.12	sqm
10	Providing & fixing of m.s. angle Iron 40x40x5 mm door chauhket in proper position at site						
		1	0.75			0.75	rm
		2	2.1			4.2	rm
		6	0.15			0.9	rm
					total	5.85	rm
				3.50kg/rm		20.475	kg
11	Providing & fixing of z section steel ventilator chauhket with sq bar grill						
		1	0.6	0.45		0.27	sqm
			35kg/sqm			9.45	sqm
12	Providing & fixing of m.s. angle Iron 40x40x5 mm for purline of g.c. sheet roof in proper position at site						
		2	3.51			7.02	rm
			3.50kg/rm			24.57	kg

NAVCHATNA KENDRA 10 ASHOK MARG, LUCKNOW, (U.P.)

13	Providing & fixing of corrugated g.c sheet roofing 1.0x3.0m blk with zinc coating not less than 275 gm/sqm with polymer coated J or I hooks and nuts 8mm dia with bitumen and g.c. limpet washer etc complete						
		1	3.51	2.21		9.51	sqm
					total	9.51	sqm
14	12MM plaster with 1:6 cement ,coarse sand mortar with all material,labour ,I&P etc complete						
	inside	1	3.05		1.52	4.54	sqm
		1	3.05		1.43	4.36	sqm
		2	1.8		1.53	5.49	sqm
	out side	1	3.51		3.20	11.23	sqm
		1	3.51		3.10	10.88	sqm
		2	2.26		3.15	18.24	sqm
		1	3.51		0.69	2.42	sqm
		2	2.06		0.69	2.84	sqm
					total	56.10	sqm
15	Providing and laying ceramic glazed tiles of 1st quality conforming to is:15622 of approved make in any colour laid on 20mmthick cement mortar 1:4 cement ,coarse sand jointing with grey cement slurry @3.3 kg/sqm including pointing the joints with white cement and matching pigments etc complete						
	wall	2	3.05		1.22	7.44	sqm
		2	1.83		1.22	4.47	sqm
	floor	1	3.05	1.81		5.58	sqm
					total	17.49	sqm
16	Providing and applying white cement based putty of average thickness 1mm of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete						
					same as item no 15	56.1	sqm
18	Finishing walls with acrylic smooth exterior paint of required shade new work (two or more coat applied @ 1.5/ltr/10 sqm over and including priming coat of exterior primer applied @7.20 kg/10sqm (sca adx, walmasta) asien,berger make.						
17					same as item no 15	56.1	sqm
18	Providing and fixing ISI marked flush door shutters conforming to is :2202 (part I) non - decorative type core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 30 mm thick ISI marked stainless steel but hinges with necessary						

NAVCHATNA KENDRA 10 ASHOK MARG, LUCKNOW , (U.P.)

		1	0.75		2.1	1.58	
					total	1.58	sqm
19	Providing & fixing of door fittings						
a.	ISI marked oxidised M. S. sliding door bolt with nut and screw etc comp. 250x16 mm	1				1.00	no
b.	ISI marked oxidised M. S. tower bolt black finish (barrel type) with necessary screw etc comp. 200x10 mm	1				1.00	no
c.	ISI marked oxidised M. S. handles conforming to IS:4992 with necessary screw etc comp. 125 mm	2				2.00	no
20	Providing & fixing of 4mm thick plain glass with putty clip wire etc complete finish in ventilator						
		1	0.6		0.45	0.27	sqm
					total	0.27	sqm
21	Painting on iron works in small areas or new wood work with one coat of ready mixed priming paint & two coat of approved superior quality ready mixed paint including supply of all materials, labour and t&p etc required for proper completion of work						
	door shutter	2	0.75		2.1	3.15	sqm
	ventl.	2	0.6		0.45	0.54	sqm
					total	3.69	sqm

SANITARY INSTALATION


1	Providing and fixing of white vitreous china orissa pattern w.c. pan of size 580x440mm with integral type foot rests with 100mm sand cast iron p or s trape, 10 litre low level white p.v.c. flushing cistern, including flush pipe manually controlled device (handle lever) conforming to IS :7231 with all fitting						1.00	NO
2	Providing and fixing of white vitreous china flat back type lipped front urinal basin of 430x260x350 mm with automatic flushing cistern with standard flush pipe and cp brass spreaders with brass unions and g.I. clamp complete including painting of fitting and bracket, cutting and making good the wall and floor wherever required one urinal basin with 5 litre white p.v.c.							

NAVCHATNA KENDRA 10 ASHOK MARG, LUCKNOW , (U.P.)

3	Providing and fixing wash basin with c.l. brackets 15mm C.P. brass pillar tap, 32mm C.P. brass waste of standard patterns, including painting of fittings and brackets, cutting and making good the walls where ever require						
	630mm*450 mm with a pair of 15mm CP Brass pillar tapes						1 NO
4	Providing and fixing Chlorinated polyvinyl Chloride (CPVC) pipes having thermal stability for hot and cold water supply, including all CPVC plain and Brass threaded fittings including fixing the pipe clamps at 1Mtr. Spacing .This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of engineer in charge. Internal work/exposed all walls.						
	15 mm nominal outer dia pipe	10	6				60.00 NO
5	Providing and fixing Soil , waste and vent pipes						
	100 mm dia sand cast iron Sn5 pipe as per IS:1729	1	20				20.00 NO
6	Providing and fixing c.p.brass long nose bib cock of approved quality conforming to IS standered and weighing not less than 810gm 15mm nominal bore	1					1.00 no

ELECTRIFICATION

1	Wiring point for light with 1.5 sq. mm.FRLSH PVC insulated multistrand single core copper conductor cable in heavy guage rigid steel conduit pipe on surface, complete with 14 SWG copper earth continuity wire, GP Box ,piano type switch and ceiling rose/angle/ batten holder on 3 mm. thick phenolic laminated backelite sheet etc. complete in all respect, as directed .	1	1				1.00 NO
---	--	---	---	--	--	--	---------


 G.
 Arc
 SS-114
 K.

NAVCHATNA KENDRA 10 ASHOK MARG, LUCKNOW , (U.P.)

2	Wiring point for fan /fresh air fan (light duty exhaust fan) with 1.5 sq.mm.FRLSH PVC insulated multistrand single core copper conductor cable in heavy guage rigid steel conduit pipe on surface complete with 14 SWG copper earth continuity wire, piano type switch & ceiling rose on 3 mm. thick phenolic laminated backelite sheet etc, complete in all respect.	1	1			1.00	NO
3	p/f of exhaust fan havells ventil air dx 200mm	1				1.00	NO